



AVM System Material and Labor Warranty Requirements (Deck and Planter)

AVM System Material and Labor Warranty Requirements (Deck and Planter)

1. *AVM System Material and Labor Warranty eligibility (reference Product Manuals for product applications and installation instructions):
 - Aussie Membrane 500 & 502 (90 mil) **10 years**
 - Aussie Membrane 520 (90 mil) **10 years**
 - Aussie Membrane 500 & 502 (120 mil reinforced) **20 years**
 - Aussie Membrane 520 (120 mil reinforced) **20 years**
 - Aussie Membrane 570 **20 years**
2. Installer: AVM products must be installed by an AVM Approved Applicator
3. Project waterproofing details must be installed in accordance with AVM's standard published and/or project specific waterproofing details. Job specific details created by AVM Approved Applicator or designer must be signed off by AVM Representative
4. Pre-Installation Conference: A pre-installation conference shall be held prior to commencement of field operations to establish procedures to maintain optimum working conditions and to coordinate this work with related and adjacent work. Agenda for meeting shall include review of special details and flashing.
5. Inspection: Project must be inspected by waterproofing applicator. Applicator must provide AVM with photo documentation of the following:
 - The entire substrate to receive waterproofing
 - Detailing work of penetrations and other critical areas
 - The completed waterproofing system prior to the installation of drain board or other protection media
 - The completed installation before rebar and concrete coverage
6. Leak Detection: Either 48-hour flood testing or electronic leak detection are required. Additional requirements may be needed for electronic leak detection depending on the application and substrate.
7. Warranty Issuance:
 - The Certified Date of Substantial Completion is required for warranty issuance.
 - *All substrates must meet AVM requirements and be primed with the appropriate primer.

